## **Quality Assurance and Testing of Facades**

# Sudhanshu Dighe FITI



## future skyline



## THE CHALLENGES



### DESIGN

### PERFORMANCE

COST

### TIME LINES

### QUALITY



### FAÇADE DESIGN REQUIREMENTS



HIGH WIND PRESSURE



#### PEDESTRAIN COMFORT







FIRE / VENTILATION

#### WORKMANSHIP DEPENDENCY

SAFETY

# Why Façade Testing?

Last chance for correction of design to meet performance.

Key to stability certification to the building.

Must for every building validation and certification.

Must for safety as a whole.



# MAIN PERFORMANCE PARAMETERS

Weather

Structural

Seismic

Thermal

Acoustics

Fire



# Weather - AIR LEAKAGE

Air Infiltration

-Under positive pressure

-Air infiltration means heat entering inside. Air Exfiltration

-Under negative pressure

-Air exfiltration means loss of cool air.

Either way is loss of air-conditioning Also loss in Acoustical performance. Cannot be verified in drawings alone.



# Air Performance Standards

• 5.76 m <sup>3</sup> /hr/m <sup>2</sup> • 1.8 m <sup>3</sup> /h	nr/m²	<ul> <li>2.06 m<sup>3</sup>/hr/m<sup>2</sup></li> </ul>	<ul> <li>0.50 m<sup>3</sup>/hr/m<sup>2</sup></li> </ul>



# Air Test Pressure



FACADE INDIA

# Weather - WATER LEAKAGE

Water Leakage

- -Under positive pressure
- -Damages interior, False celling and furnishings.
- -Ineffective utilization of floor space near façade perimeter.
- -Fungal growth
- Cannot be verified in drawing alone. Scientific system design to be Followed.



# Water Test Pressure



Testing Inc

### SIESMIC & LIVELOAD MOVEMENTS



UNITISED WITH SLIDER STACK JOINT

### Intermediate Floor Drift

- 0.4 % of Floor Height L/250
- Flexible Joints at Floor Level to Release Forces.
- Cast In Chanel With T-Bolt Allowing Movement.



## PERFORMANCE TEST SEQUENCE

- 50% Structural load -
- Vent Open Close 5 times
- Air Infiltration test 300Pa (As per ASTM E 283)
- Static Water Test 450Pa (As per ASTM E 331) –
- Dynamic Water Test 450Pa (As per AAMA 501.1) –
- Structural Wind load Test 1000Pa (As per ASTM E 330)
- Repeat Static Water Test 300Pa (As per ASTM E 331) –
- Proof Load Test 1500Pa (As per ASTM E 330)





Case Study – Kohinoor Square

Diamond Skin Design



## ARCHITECTURAL REQUIREMENT

Articulated Façade Vision glass inclined outward & inward.

Spandrel glass inclined inward & outward.

Profile fin projection visible in elevation.



### WIND ANALYSIS

Wind Pressure Zoning

2 – 2.75 Kpa 3 – 3.25 Kpa 3.5 – 4 Kpa 4.25 – 5.25 Kpa – 10 %

System Design

### 4 Kpa

Remaining 10% after checking the reserve strength.





Articulated Unitized system -1.5 m x 3.9 m units 250mm Deep profile.

Glass articulation in Mullion Fin projection.

Telescopic base profile to receive articulation.

#### ENGINEERING OF GLASS



High reflective glass.

Vision glass - 32mm IGU glass of 1.5 m x 3.0 m (8 +16AG+8)

Glass fabrication Quality - Flatness of glass within 2 mm.

Annual weather cycle 20% of DWP (800 Pa)

Pressure drop at height



### **DESIGN VALIDATING**

Design validation by performance test process carried out at Laboratory.

Air leakage test at 300 Pa.

Water leakage test at 750 Pa- 1200 Pa – 1500 Pa.

Wind load serviceability test at Step 1 – Passed 4 kpa. Step 2 – Passed 6 kpa. Step 3 – Reserved strength of 7.3 kpa.

Seismic inter story floor drift at 15mm.



### Case Study – Brigade Gateway, World Trade Centre

### Skewed Glazing System



#### ARCHITECTURAL REQUIREMENT

Vision glass skewed in Plan.

Spandrel glass straight in plan.

Visible mullion 200mm deep as Fin projection (South elevation)

Façade curved in plan.



Vision glass – Floor to Celling – 1.5m x 3.6 m Wind pressure – 1.6 kpa ENGINEERING OF GLASS

Glass fabrication Quality - Flatness of glass within 2 mm.

Annual weather cycle 20% of DWP

Pressure drop at height.



Unitized Element Design - 1.5m x 4.2m units

#### SYSTEM DESIGN

System – Structurally Glazed with mechanical holding

250mm Split mullion with 3 barrier gasket system.

200mm deep mullion projection acting as vertical Fin.



## **DESIGN VALIDATING**

Design validation by performance test process carried out at Laboratory.

Air leakage test at 300 Pa.

Water leakage test at 600 pa

Wind load serviceability test at Step 1 – Passed 1.8 kpa Step 2 – Passed 2.7 kpa

Seismic inter story floor drift at 24mm.

### THANK YOU

